

TENTATIVE SPACE REQUIREMENT

PROJECT NAME	DASHRATH MANJHI INSTITUTE OF LABOUR AND EMPLOYMENT STUDIES AT PATNA				
PROJECT IMPLEMENTATION AGENCY	BIHAR STATE BUILDING CONSTRUCTION CORPORATION LTD, PATNA				
LOCATION	B.M.P.(BIHAR MILITARY POLICE)AREA,NEAR JAI PRAKASH NARAYAN AIRPORT,PATNA				
PLOT AREA	4047.40 Sq.Mtr				
Sr.no.	ITEMS	PARTICULARS	QUANTITY	SPACE (SQ. Mtr)	
A	ADMINISTRATIVE				TOTAL
1		RECEPTION/REGISTRATION		40	
2		WAITING LOUNGE		40	
3		V.I.P.WAITING LOUNGE		25	
4		DIRECTOR CABIN (TOILET)		30	
5		GENERAL OFFICE		60	
		TOTAL			195
B	ACEDEMIC				
		LECTURE HALL	5	50	250
6		SEMINAR HALL(WITH AUDIO VISUAL)	1	150	150
7		WORK SHOP (TRAINING)	1	400	400
8		TRAINING HALL	2	150	300
9					
		TOTAL			1100
C	HOSTEL				
10		ROOMS WITH ATTACH TOILETS	50	30	1500
11		KITCHEN	1	50	50
12		DINING HALL	1	200	200
13		RECREATION- T.V.LOUNGE	1	50	50
14		GYM	1	100	100
		TOTAL			1900
D	COMMON FACILITY				
15		COMMON TOILETS (GENTS+LADIES)	2	20	40
16		STAIRCASES	2	20	40
17		SECURITY	1	10	10
18		TIME OFFICE	1	10	10
19		STORE	1	20	20
		TOTAL			120
E		TOTAL A+B+C+D			3315
	ADD	FOR WALLS & CIRCULATION AREA	25%		828.75
		GRAND TOTAL			4143.75
	TOTAL BUILT UP AREA MAY BE LESS THAN 4200 Sq. Mtr.				