

बिहार राज्य भवन निर्माण निगम, लि० पटना

(बिहार सरकारका उपक्रम)

दर आमंत्रण हेतु कोटेशन आमंत्रण सूचना सं०-61/2018-19

भवन निर्माण विभाग के निबंधित संवेदकों/ख्याति प्राप्त फर्मों/कंपनियों से दिनांक: 10.09.2018 के अपराह्न 3:00 बजे तक निर्देशानुसार निम्नलिखित कार्यों के लिए मुहरबंद कोटेशन उप महाप्रबंधक, पी०आई०यू०, पटना/महाप्रबंधक (उत्तर/दक्षिण)/मुख्य महाप्रबंधक, बिहार राज्य भवन निर्माण निगम लि०, पटना के कार्यालय में प्राप्त किया जाएगा और उसी दिन 3:30 बजे अपराह्न में कोटेशनदाताओं या उनके द्वारा अधिकृत प्रतिनिधियों के समक्ष खोला जायेगा।

कार्य का विवरण:-

क्रम सं०	योजना का नाम	कार्य की विवरणी	ईकाई	उद्धृत दर
1	2	3	4	5
Civil & Electrical Work				
1	Provisions of Chamber of Minister, room for official Person, court yard beatification & furniture of Dashrath Manjhi Institute of Labour and Employment Studies Patna	Providing and fixing TATA BLUESCOPE LYSAGHT COLORBOND Trapezoidal TRIMDEK profile sheet Of 1015mm effective cover width and nominal 28.5mm deep rib with subtitle square flutting in the five pan at nominal 200mm c/c .The end rib shall be designed for anti-capillary action. To avoid any seepage of water through the lateral overlap. The feed material is manufactured out of BMT 0.45 having,TCT1 of 0.5 mm ,HI-tensile steel with minimum 550MPA yield strength metlic hot deep coated with aluminium, Zinc alloy ,55% aluminium 43.5% zinc and 1.5% silicon as per As 1397 Zincaalume as AZ 150 minimum 150 GMS per Square meter total all both side. There after providing sub girt in 1.5mm thickness in Z shape of 50mm Web and 50mm flange over bottom Skin sheet shall be 0.47mm thick baregal volume LYSAGHT trimdek sheet of TATA BLUESCOPE.	SQM	
		Land Scaping	Each	
2		Supplying of different type of ornamental plant etc. aii complete job as per direction of E/I		
(i)		Eliocasia	Each	
(ii)		Ragon	Each	
(iii)		Hobiya	Each	
(iv)		Boganbaliya	Each	
(v)		AricaPam	Each	
(vi)		Cicus	Each	
(vii)		Fikus	Each	
(viii)		Sampian Pam	Each	
(ix)	Jamiya	Each		
(x)	Cocopit	Each		
(xi)	Milli	Each		
3		Supplying of different type of seasonal flower plants etc. all complete job as per specification and direction of E/I	Each	
(i)		Supplying and fitting Artificial grass	Sqm	
(ii)		Electrical		
4		Compact pre fabricated packaged sub station 11kv/433 volt.		
		Packaged Sub station 11kv/433v consisting of 3 way SF6/VCB insulated compact RMU, oil cooled /dry type copper wound transformer and L.T. section with one ACB as incoming and 7 no outgoing MCCB feeders and with encloser made of electronically		

