

बिहार राज्य भवन निर्माण निगम, लि० पटना
 (बिहार सरकार का उपक्रम)

दर आमंत्रण हेतु कोटेशन आमंत्रण सूचना सं०-73/2018-19

भवन निर्माण विभाग के निबंधित संवेदकों/ख्याति प्राप्त फर्मों/कंपनियों से दिनांक: 15.09.2018 के अपराहन 3:00 बजे तक निर्देशानुसार निम्नलिखित कार्यों के लिए मुहरबंद कोटेशन उप महाप्रबंधक, पी०आई०यू०, पटना/महाप्रबंधक (दक्षिण)/मुख्य महाप्रबंधक, बिहार राज्य भवन निर्माण निगम लि०, पटना के कार्यालय में प्राप्त किया जाएगा और उसी दिन 3:30 बजे अपराहन में कोटेशनदाताओं या उनके द्वारा अधिकृत प्रतिनिधियों के समक्ष खोला जायेगा।

कार्य का विवरण:-

क्रम सं०	योजना का नाम	कार्य की विवरणी	ईकाई	उद्धृत दर
1	2	3	4	5
CIVIL & PH WORK				
1		Supplying all labour, T&P for the Carriage of excavated earth by mechanical means of transport within 5.00 K.M. lead including hire and running charges of vehicles, labour charges for loading and unloading as required for the work etc. complete as per the direction of the Engineer-in-charge.	Cum	
2	पटना जिलान्तर्गत पटना में अंजुमन इस्लामियाँ हॉल का पुनर्निर्माण कार्य।	Checking the leakage & seepage with ponding test & application of FOSROC Brush bond RFX or Sika Top seal 109 hi Two Coats over the toilet & basement reinforced & primed with Sika Top Seal 109 hi primer. Coving with 1:4 Cement mortar admixed with FOSROC Cebex 100(225 gms/50 Kg Cement) or Sika Pastorate Super (100 gms/50 Kg Cement) over the joints to Terrace to parapet over a bond coat of FOSROC Nitobond SBR Latex or Sika Latex (1:4:6) followed by a protection screed (1:1.5:3) in panels of size 2mtr x 2mtr to drain the water towards the rain water pipe & finally filled the joint grooves (10mm x 10mm) with Polyurethane Sealant FOSROC Nitoseal PU 40 or Skiabile Construction AP/Polysulphide Sealant complete as per manufacturer specification and direction of Engineer-in-charge.	Sqm	
3		Providing and fixing a 4mm thick Pre-applied Polypropylene waterproofing membrane for raft and retaining wall in basement, waterproofing membrane shall be mechanically bonds to poured concrete & remains in place if settlement of substrate occurs. Pre-applied Polypropylene waterproofing membrane shall have complex cell mesh bonded to a polyethylene membrane, which allows poured concrete to interlock with the membrane forming a tenacious mechanical bond. The membrane shall be supplied with one self-adhesive selvedge to provide sealed laps and comply with British Standard 8102 2009 - Code of practice for "Protection of Structures Against Water from the Ground" to provide basement waterproofing protection to grades 1, 2 and 3. The product shall be	Sqm	

	BBA certified and approved by Green Label Singapore Labelling Scheme. It shall comply with the requirements of BS EN 13967:2004, Type A and Type T, "Flexible sheets for waterproofing- Plastic and rubber damp proof sheets.		
4	GRC Column(Decorative col)	Cum	
5	System: Providing and applying Nitoproof 600 Standard single component polyurethane cures by reaction with atmospheric moisture to give a tough elastomeric waterproof membrane; Nitoproof 600 Standard is a medium viscosity grade (approximately 600 poise) and has a 620% of elongation. It is supplied in a single grade to meet all site application methods and requirements. Shall be Brush application for thickness of 1.3mm . . Properties Typical cured membrane properties (at 28 days), Elongation (ASTM D412) : 620 %,Tear resistance (ASTM D624) : 15 N, Shore A hardness (ASTM D2240) : 50, Extensibility after heat aging (min. requirement -extended to 6.4mm,without cracking) : No cracking or tearing, Service temperature (continuous ambient) : -40°C to 70°C. System includes surface preparations, supply, application and complete as per the fosroc methodology .	Sqm	
6	Providing fixing of Hand rail made with steel hand rail with glass	Rm	
7	Providing for GRC Wall & Parapet	Sqm	
8	Providing UPVC Windows with full reinforcement, glass fitting ,casement handle including fitting and installing charges and also including site supervision incharge charge	Sqm	
9	Providing UPVC TOILET DOORS with full reinforcement, glass fitting ,casement handle including fitting and installing charges and also including site supervision incharge charge	Sqm	
10	Providing FACTORY MADE ENTRANCE DOOR	Sqm	
11	Providing wood work in STAGE and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately).	Sqm	
12	BOUNDARYWALL		
	GRC Work	Sqm	
	ROAD		
	Supplying & laying of Granular Sub Base Grade II	Cum	
13	R.C.C. work of M-20 for 4"perforated slab at drain including hoisting, lowering, laying and compacting concrete with vibrator, watering and curing for 28 days	Sqm	
	50mm thk Screed(1:2:4):at drain and Sloping at road Lvl	Cum	
15	Providing flooring using interlocking tiles of premium grade having thick of 100mm	Sqm	
	Compaction of Sub grade Lvl	Sqm	
	PH WORK		
16	BORING. S/F/F 5 H.P SUBMERSIBLE PUMP OF ISI MARK WITH STARTER,PANNEL ,CABLE ,WELL		

	COVER ETC. Providing & fixing of STANDARD MAKE as per Instructions Engineer -in-charge.		
	SWERAGE TREATMENT PLANT (STP)	Each	
17	Supply installation testing and commissioning of Monobloc Raw Effluent transfer pumps of capacity 2 cum/hr @ 25 m head.(1W + 1S) .	Nos.	
18	Supply Installation, testing and commissioning of Centrifugal Filter Feed pump of capacity 5 cum/hr @ 35 m head (1W + 1S)	Nos.	
19	Supply, installation, testing and commissioning of Bar Screen - Fabricated out of SS - 304 with openings of suitable size	Nos.	
20	Supply, installation, Testing & Commissioning of Coarse pore Diffuser of suitable size in engineering plastic as per manufacturer's recommendation etc, complete.	Job	
21	Supply, installation, Testing & Commissioning of Fine pore Diffuser of suitable size in engineering plastic as per manufacturer's recommendation etc, complete.	Job	
22	Supply, Installation, Testing & Commissioning of 75 cum/hr at 0.5 ksc capacity Air Blower with motor, drives etc., complete. (1W + 1S)	Nos.	
23	Supply, Installation, Testing & Commissioning of Decanter Mechanism - 100 NB with automated motorized valve	Nos.	
24	Supply, Installation, Testing & Commissioning of Centrifugal Sludge Transfer Pumps of capacity of 4 cum/hr at 10m head (1W+1S)	Nos.	
25	Supply Installation, Testing & Commissioning of MS Pressure Sand Filter for a flow rate of Cum /hr 800mm dia x 1500mm HOS with all internals, inlet, outlet, backwash piping valves, pressure gauges, filter media etc., complete.	Nos.	
26	Supply Installation, Testing & Commissioning of MS Activated Carbon for a flow rate of 10 Cum /hr 800mm dia x 1500mm HOS with all internals, inlet, outlet, backwash piping valves, pressure gauges, filter media etc., complete.	Nos.	
27	Supply, installation, testing & Commissioning of Chlorinator of capacity 0 to 6 Lps with metering pump of reputed make with inlet, outlet piping etc., complete.	Nos.	
28	Piping Works :Supply, laying, jointing, testing & commissioning of Rigid CPVC/ UPVC 10 Kg/cm ² pressure pipes of suitable size for interconnected piping works with all specials, fittings, isolation valves, etc., and with required valve chambers, chamber covers etc., complete. Rate quoted should also include for supplying & providing GI puddle flanges for sumps. Provision in terms of puddle flanges, valves, etc .	Job	
29	Supply, laying, jointing, testing & commissioning of GI "C" pipes of suitable size for interconnected piping works with all specials, fittings, isolation valves, etc. and with required valve chambers ,chamber covers etc. complete. rate quoted should also include for supplying & providing Gi puddle flanges, valves etc.-for Blower Air Line with necessary accessories	Job	

- यह कोटेशन दर निर्धारण के लिए आमंत्रित किया गया है।
- विशेष जानकारी हेतु अधोहस्ताक्षरी के कार्यालय में कार्यावधि में सम्पर्क करें।

विशेष शर्तें:-

1. कोटेशनदाताओं को अपना दर अंक एवं अक्षरों में उद्धृत करना है।
2. दर सभी प्रकार के करों को लेकर अंकित किया जायेगा।
3. दर कार्यस्थल पर समानों की दुलाई को लेकर किया जाएगा, उन्हें किसी प्रकार का अतिरिक्त दुलाई दर देय नहीं होगा।
4. कोटेशन के साथ अद्यतन आयकर एवं GST प्रमाण-पत्र देना होगा।
5. विशेष सूचना के लिए सूचनापट्टा या वेबसाइट www.brdbihar.gov.in एवं www.bsbcccl.bih.nic.in देखें या अधोहस्ताक्षरी से सम्पर्क करें।

ह0/-

मुख्य महाप्रबंधक,

बिहार राज्य भवन निर्माण निगम लि0, पटना।

ज्ञापांक:-

दिनांक:

प्रतिलिपि:- निदेशक, सूचना एवं जन-सम्पर्क विभाग, बिहार, पटना को e-advertisement के माध्यम से दैनिक समाचार पत्रों में प्रकाशनार्थ समर्पित

ह0/-

मुख्य महाप्रबंधक,

बिहार राज्य भवन निर्माण निगम लि0, पटना।

ज्ञापांक:-

2602

दिनांक:

30.8.18

प्रतिलिपि:- आई0टी0 मैनेजर, बिहार राज्य भवन निर्माण निगम लि0, पटना को सूचनार्थ एवं निगम के वेबसाइट पर अपलोड करने हेतु प्रेषित।

मुख्य महाप्रबंधक,

बिहार राज्य भवन निर्माण निगम लि0, पटना।

bx